

The Project

- Area Wide Treatments
- Design 2003
- · Construction 2003/04

200E 42 4E 44 4E

The Site

- 700m section SH5 Napier-Taupo
- Mode of Failure
 - Cracking
 - Flushing
 - Rutting
- Original 1950s construction (with repairs)
- · Built on a fill

2005.12.15 11.15

Investigations

- Testpits
 - Thick existing seal layers
 - 220mm greywacke AP65
 - Pumice sand subgrade
- FWD
 - Deflections average 2.1mm
 - 85%ile 2.5mm
 - Range 0.8mm to 3.2mm

2005 12 15 11 15

Design

- APDG 1992 / NZ Supplement May 2000
- Precedent Method
- Subgrade Model
 - Vertical modulus 10CBR, horizontal 5CBR
- No sub-layering required
- 100mm overlay with TNZ M/4
- Cement modify 2%, recycle to 250mm

2005.12.15 11.15

Construction

- Constructed in two 350m sections
- · Direct water injection
- Dacite basecourse ex Tauhara
- Sealing soon after compaction
- Target densities not established
- Some density measurements not done
- · Wet weather

2005 12 15 11 15

Problems

- Within 6 months ruts noticed up to 20mm, in discrete areas
- Ruts now widespread, typically 20mm to 25mm
- Cracking and pumping of fines
- Several post-construction testpits dug
- Pavement in wheeltracks is not well cemented

2005.12.15 11.15

Issues/Points for debate

- · Enough protection for subgrade?
 - No clear evidence of subgrade deformation
- Design for subgrade strains?
 - Resulting pavement extremely thick
 - Upper limit for subgrade strain?
- Issue with materials?
 - Lack of "fine fines"
 - Material complied with TNZ M/4
- Was sufficient compaction possible?
 - Particularly for this material

2005.12.15 11.15

Suggestions for Change

- Use of repeated load triaxial testing to determine durability (even for M/4)?
- Develop new relationships for sub-layer moduli on volcanic subgrades?
- Cap allowable subgrade strain (as % of Austroads strain criterion)?

2005.12.15 11.15